
## WINDOW LIFT MOTOR REPLACEMENT PROCEDURE

NOTICE

## 1994-1991 AEROSTAR & 1991 E SERIES VAN

For these applications it will be necessary to remove the molded connector and reverse wire positions in relation to the locking tab as shown below. Remove molded connector by moving connector locks toward the center of the connector. Even though the motor connections at the motor are on the bottom instead of the top, this replacement motor will install like the original.



## 1992 THRU 1987 BRONCO II AND RANGER (BUILT AFTER 11/1/86).

Cut the wires with connector from the old motor. Cut the connector from the new motor. Attach old connector to new motor temporarily usuing red to yellow and yellow to red. After installing motor in the door make sure switch matches motor rotation. If rotation is correct connect wires with splicers included and reattach trim.

UPDATED 06/2022 Form 82732-265\_EN